PEEM-S100 WiFi Smart Meter_User Manual _ EN

Update Instructions

This section records the updates of the Smart Meter User Manual.

Version	Update Date	Content
V1.0	2024-11-8	Initial version

Read Before Use

This manual contains important instructions for Smart Meter, which must be read completely before installing or debugging the equipment. For safety reasons, only qualified technicians who have been trained or have proven skills can install and maintain this Smart Meter under the guidance of this document.

This manual is applicable to the following products:

Model	Communication	Installation Mode	Wiring Mode
PEEM-S100	WiFi	DIN Rail	CT Connected

The following security symbols are used in this manual. Before installing or operating the system, familiarize yourself with these symbols and their meanings.

Identification	Explanation
\triangle	Danger: Danger indicates a dangerous situation that may cause fatal electric shock, other serious personal injury, or fire danger.
Â	Warning: Warnings indicate instructions that must be fully understood and followed to avoid potential safety hazards, including equipment damage or personal injury.
Â	Note: Notes indicate that the described operation should not be performed. Before continuing, readers should stop using and

Product Introduction

System Introduction

Smart Meter is a power meter that uses WIFI communication. It is installed in the home distribution box, collects voltage, current, power and other information of the power grid, and transmits it to microinverter or micro storage unit through the WIFI network. It assists microinverter or micro storage unit in performing control functions such as zero-export function.

Example : Smart Meter and TSUN Products integrated with WiFi



Product Introduction



А	Connector	D	Screen
В	Antenna Port	E	Buttons
С	Status Light		

Product Installation

Confirm the Phase of the Circuit

If this smart meter is installed on a single-phase power grid, ignore this section and proceed to the next step, "Install the Smart Meter".

If this smart meter is installed on a three-phase power grid, it is necessary to confirm the installation position of the meter according to the following method. Confirm the corresponding switch and the phase of the microinverter or micro storage unit in the household distribution box. As shown in the figure below, it is necessary to confirm which phase of the microinverter or micro storage unit is in. The smart meter must be installed next to the electricity meter. When the meter is in the same phase as the corresponding microinverter or micro storage unit, the microinverter or micro storage unit can turn on the zero export function.



• Method 1:

If the circuits or devices controlled by each switch are clearly marked on each singlephase switch in the household distribution box, the installer can directly find the circuit switch that controls the microinverter or micro storage unit.

• Method 2:

If the control circuit of each single - phase switch in the household distribution box cannot be clearly distinguished, the installer can consult the household about the house power grid wiring diagram, obtain relevant information by querying the drawing, and find the circuit switch that controls the microinverter or micro storage unit.

• Method 3:

If relevant information cannot be found in the distribution box or drawing materials, the installer can quickly find the corresponding circuit switch according to the following steps.

1. Step 1: Connect an easily-observable household appliance (such as an electric fan, desk lamp, etc.) to the socket that is ready to have the microinverter or micro storage unit installed.

2. Step 2: Turn on the household appliance and put it in working mode (for example, turning on the electric fan or desk lamp).

3. Step 3: Turn off the single-phase switches in the household distribution box one after another, and observe the status of household appliances at the same time. If the household appliance used for observation stops working after closing a single-phase switch (for example, the electric fan stops rotating, the desk lamp goes out), then the single-phase switch is the control switch of the corresponding circuit.

After finding the corresponding circuit switch, install the smart meter on the bus (or connection line) between the three-phase switch and the single-phase switch. For example, if the smart meter is installed in the L1 phase, the wiring should be as follows.





Warning:

The maximum passing current of the Smart Meter is 100A. The load current in this circuit cannot exceed this upper limit.

Pre-installation Check

Check the Product and Accessary

Although TSUN's products have passed stringent testing and are inspected before leaving the factory, it is possible that the products may be damaged during transportation. Please check the product for any obvious signs of damage. If such signs are present, contact your dealer as soon as possible.



Check the Installation Environment and Location

When selecting the installation location, the following conditions should be adhered to:

- Install the PEEM-S100 close to or within the home distribution box.
- Avoid electromagnetic interference that could affect the proper operation of electronic equipment.

• Use a mobile phone to assess the Wi-Fi signal strength at the installation site. If the Wi-Fi signal is weak, attempt to install the PEEM-S100 at an alternative location or relocate the Wi-Fi router.

Install the Smart Meter

• Step 1: Turn off the three-phase switch and all single-phase switches of the distribution box.



Danger:

Installers must ensure that the three-phase switch as well as all other switches remain in a closed state during the whole operation process. Meanwhile, be cautious not to touch the exposed conductive part on the grid - side of the three - phase switch to prevent electric shock. • Step 2: Install the Smart Meter on the rail of the distribution box.



• Step 3: Connect the L (Live) and N (Neutral) cables to port 11 and port 14 respectively. Then connect the CT cable to port 4 (using the Red Cable) and port 5 (using the Black Cable).



• Step 4: Mount the CT onto the correct L cable. The arrow direction marked on the CT should be oriented towards the inverter side.



• Step 5: Connect the Wi-Fi antenna cable to the PEEM-S100. Place the antenna outside the distribution box to ensure a strong Wi-Fi signal.



• Step 6: Upon confirming the correct wiring of the meter, turn on the three-phase switch and the single-phase switch.

Monitoring System

Download and Install APP

Download and install the "TSUN Smart" APP.

1. IOS users can directly search for "TSUN Smart" in the APP Store and download the software.

2. Android users can directly search for "TSUN Smart" in Google Play and download the software.

3. Android users who cannot access Google Play can scan the QR code below to download and install "TSUN Smart".



Register an account and log into the APP.

When registering, you can choose to be an installer or an end-user.

The rooftop solar plant which uses microinverters needs to be built by a professional installer. Please register as an "installer" and follow the subsequent instructions to execute the APP operation.

The DIY balcony storage plant which uses micro storage units is built by end - users, but the installation of smart meter still needs to be done by professionals. Please register as "end - users" and follow the subsequent instructions to execute the APP operation.



V1.0.6

Operation Steps (Professional Installer + Microinverter)

• Step 1: Click "+" to create a soalr plant. After filling in the plant information, click "Save" to complete the solar plant creation.





• Click "Add Datalogger" and scan the QR code on the meter to complete the device addition.



• First, click "..." in the upper right corner and select "WIFI Configuration". Then select the corresponding meter and click "Start Config". Finally, select the WIFI you want to connect to, enter the WIFI password and click "Start Config" again.

18:55 A	:: 🗢 🖾	18:55 A		:: † CD	18:55 A		- † 6 0	18:50 🕸		: 🗢 🚳
< Meter Test	合 …	< Meter Te	st	¢7	<	Configuration	+ Add	<	WiFi Selection	
P tocomplete O Ho Alerts	Control Policy Settings	******* 0	Consumer	Control Policy . Settings	Select the de 1. Devices card 2.40 network) 2. Devices in gr	rice to config the WiFi net connect to S0 natwork. Pleasing can't do the multi-configur	twork ie change to atien,	Enter WiFi pa This device car 2.40 network	issword I't connect to 50 network. Pla	asa change fa
•	A A A			A an	3. I i i i i i i i i i i i i i i i i i i	ing three different types of g t networking at the same tim are devices of the same type	eleways, it e, you need to before	TSUNESS		Change
		4			4 The type of networking, it e 5. Swipe left to	gateway does not support to oports one device at a time, delate the device.	di.	Need a passi	word?	0
					He Logger: 2	613159881 📮				۵
🤲 66.2°F	Last spdate	66.2°F								
Solar Consumption	Grid	\oplus	2	(:-						
	Power	Add Datalogger	Plant info	WiFi Configuration						
0 %	Callecity	8	8	æ						
	10 kWp	Layout	Authorizations	Anti-Reverse Flow Configuration						
Daily Energy	Monthly Energy									
Yearly Energy	Tatal Generation	Delete Plant								
Part Contract	道		Cancel			Start Config			Start Config	

After approximately 10 seconds, the WiFi configuration will be completed successfully, and the meter data will be uploaded to the server.

1	4:15	::: † G	18:51 🕜	::! 중 99	18:52 🕇	::! 숙 99
<	WiFi Selection	<	Device Co	nfiguration	< Device	Configuration
Enter M This de 2.40 m	WiFI password wice can't connect to 5G network. Pl stwork!	ease change to				
Ne	Checking Wi-Fi network Continue to configure network afte connected successfully.	r Wi-Fi	Please keep your pho	one close to the device.	Configura	ation Successful
T:	Checking Wi-Fi transmis speed	sion	Logger 2	Configuring	An de rices connecter	
	Cancel					
	Start Config				Complet	ed Configuration

• Step 4: Enter the "Device" page and click "Meter Configuration". Set the installation site to "Grid" and set the arrow to "Energy Purchase". Click "Save" and finish the configuration.

09:08 🔌	::!! ? 94	09:08 🕸	::!! ? @	09:08 X	::!! ? 64
< Meter Test	合 …	Can Mete	er C Save	< Meter Test	습 …
Meter Logger		2613503987-00	001	Meter Logger	
Device Status	All \sim	CTI		Device Status	All \sim
Meter 2613503987-00001	• Normal	Apply to	O Single-phase System	Meter 2613503987-00001	• Normal
Not Configured	Meter Configuration	CT CT1		Configured	Meter Configuration
	Device Control	Installation Site	Grid >		Device Control
		Energy Purchase Grid Feed-in Click arrow	v to switch		
Plant Overview	Devices Alerts			Plant Overview	Devices Devices

• Step 5: Click "..." on the plant home page and click "Anti-Reverse Flow Configuration". Choose "Turn On" and set the total plant power and offset value

(Normally set to 0 W). Reconfirm all the information and click "OK". Waiting for around 300 seconds and complete this configuration. Check the status in the device list after the configuration.



< G3 Mills	LNK.	-	< Anti-Reverse Flow Co	figuration	< Configure	Anti-Reverse Flo	< Configuratio	n Result	< TEST	TITAN防逆流	*
	-	Constituting , Server	Please Notice (, what configuring acti-evenue forum, a power statistic react to be only and 2. To evenue without the same type, and evenue without the same type.	d desires power the it for configured for	Please Notice The following card to all descens unde configured for anite	spectrum information will be applied the power station that are to be reserved flow	Configuration Ended 2024/4 UTC+00:00 1. The system will accomplicatly have 2. Configuration share when main	15/29 15:12:12 Hy when configuration on failures over 200	Meter M Device Status	Microinverte	Logger Al ~
		1 *	Microinverter	factor Provent	Anti-Reverse Flow Se	witch Status	seconds, please check the device 1. More eventer devices with an shipley the corresponding status	i reverse flow enabled will in the design list.	Microinverte	e S.	4 Alerto
20°C		and shares the same			Total Rated Power of Them an about of Tree statistics, with a statistication The data range that can	the Power Station opinveriers under the current power power of 30300 to to act 1 - 6530 to	Microinverter vr3e3enp1ercoap	C Recoveried			Device Control
						w					
And Decemper	Parciela	Riff Configuration			Anti-reverse flow por The data range that can	wer offset value be set: 02708-3226739					
*	8					w					
Layout	Authorizations	Anti-Reverse Flow Configuration				Kars Config					
Delete Plant			No.				Ind Carlie	and in a	10		÷
	cancel	111	19985		33	2.8	Line County	and the second se	Photo Station	Annal .	- 10.0

Operation Steps (DIY End-Users + Micro Storage Unit)

• Step 1: Click "Create Plant". After filling in the plant information, click "Save" to complete the plant creation.

15:44 🛝	::: 🗢 98	15:44 🖌	::! ? 88	15:45 A	::: 🕈 🚥
Plant	=	< Create	Plant	< Cr	eate Plant
		Plant Name*		Plant Name*	
		's Solar Plant		TSUN's Solar Plant	
		Region*		Region*	
			~	China Jiangsu Suzh	ou Xiangchengqu 🛛 👻
		Plant Address*		Plant Address*	
				Create a p	plant successfully!
No plants in this accou	unt!	Capacity*		Click 'Switch I	Plant' and Check Details
Create Plant		Please enter PV capacity	Wp		Č.
		Commission Date*		Commission Date*	Sure
		2024-11-11	⊞	2024-11-11	m
		Total Cost		Total Cost	
		Please input total cost	CNY ~	Finance input total of	
		Plant Photo		Plant Photo	
		â		(A)	
ш 🕮	2	Sav	e		
Plant History	Me				

• Step 2: First, click menu button in the upper right corner and then select "Device List". Next, click "Add Device" and under the "Accessories" menu, select "Smart Meter" device. Finally, scan the QR code on the meter to complete the device addition.

15145 A	at 🕈 🚥	15:45 8	nt * C)	15:45 8		nt * CD	15:45 A			
TSUN	s Solar Plant. 📃	<	Device List	<	Add Devic	•	<	Scan		
	e ¹ Switch Plant			(1) Please safe	et the device type	to add		-		
6	Plant Setting			Microinverter	11		And in case of the local division of the loc			
1	11. Device List			Storage Unit	DTU	South Matter	1000			
	S, Authorization settings			Accessory			and the second second			
	(k) Benefits Calculator						100 Careto 100		r	(T)
	Control Strategy									Ø 0
10.817 Santas	A time		No equipment					Carlos and		
Contraction of	DIT Manual						1000	And the second second		
A Trees from the										
▲5 (0.1 kg	An Internet	+ nar tao	er Vi Alf Gelig		_		Euros Tuongos	Not the Cill coder The Cill Social Photos		PWO: xxxxxxxx

• Step 3: In the "Device List", click "WIFI Config". Select the corresponding meter and click "Start Config". Select the WIFI you want to connect to, enter the WIFI password, and click "Start Config" again.

18:50 🛝		:::: ? 00	18:55 🛝		III ବ 💷	18:50	a	::: † @D
<	Device List		<	Configuration	+ Add	<	WiFi Selection	
ሳሳ Meter: 261315 2613159881	9881-00001		Select the dev 1. Devices can't 2.4G network!	vice to config the WiFi n connect to 5G network. P	network lease change to	Enter WiFi This device 2.4G networ	password can't connect to 5G network. I kI	Please change to
			 Devices in gra Devices in gra<td>ay can't do the multi-contr ting three different types o rt networking at the same ore devices of the same ty</td><td>guration. If gateways, it time, you need to pe before</td><td>TSUNESS</td><td></td><td>Change</td>	ay can't do the multi-contr ting three different types o rt networking at the same ore devices of the same ty	guration. If gateways, it time, you need to pe before	TSUNESS		Change
			4. The type of networking, it su 5. Swipe left to	gateway does not suppor upports one device at a tin delete the device.	t bulk ne,	Need a pa	ssword?	
			M Logger: 2	613159881 📴				8
+ Add Devic	ie 🔶 M	/iFi Config		Start Config			Start Config	
_								

After approximately 10 seconds, the WiFi configuration will be completed successfully, and the meter data will be uploaded to the server.

14:15	#!! \$	G 18:5	10	::!! ? @)	18:52 🕈	::!! ? 99
<	WiFi Selection	<	Device Configu	ration	< Device	e Configuration
Enter WiFi ; This device c 2.4G network	bassword an't connect to 5G network. Please cha d	inge to				
Ne	Checking Wi-Fi network	Pleas	se keep your phone clo	se to the device.	Configu	ration Successful
T:	ecking Wi-Fi transmission eed	ት Logg 2013	ier 📮	Configuring	All devices connect	ed to the network successfully.
	Cancel	H				
	Start Config			_	Comple	eted Configuration

• Step 4: Click menu button on the plant home page and click "Control Strategy".

Click "Go to Contiguration" . Turn on the Anti-Reverse Flow Contiguration.



Appendix:

PEEM-S100

AC Input	Grid Type	Single phase
	Input AC Voltage	230V
	Input AC Frequency	50 / 60 Hz
	Max. Current per phase	100A
	Power Consumption per phase	<1W
Communicatio n	Wi-Fi Туре	WIFI (802.11 b/g/n)
	Wi-Fi Frequency Range	2400MHz-2483.5MHz
	Maximum Distance to Router (Open Space)	100m

	Bluetooth Type	BLE 5.0
	Bluetooth Frequency Range	2400MHz-2483.5MHz
	Maximum Distance to mobile phone (Open Space)	50m
Control	Connection Limit	5 Microinverters
	Communicate to Server	300 s
	Communicate to Microinverter	300 m s
Accessary	External Antenna	Yes
	Cable length of antenna	2 m
	External CT	1
	Cable length of CT	2 m
	СТ Туре	16mm
Mechanical Data	Dimension(mm)	36 * 90 * 90
	Weight (g)	130
	Ambient Temperature(°C)	-20~+55
	Mounting System	Rail mounted (35mm)
	Indicator Light	1 * LED
	Altitude(m)	< 2000
	Relative Humidity	0 - 95%, No condensation